

CHAPTER IV

CONCLUSION

Based on the results of the discussion in this report, several conclusions can be drawn related to the existing problem formulation. Formwork must be strong enough to support the weight and pressure of the concrete at the time of placement without causing. In this project, formwork is needed to form columns, beams, slabs, and walls in casting works in structural works. From the calculation of vertical formwork statical analysis we can conclude that using phenolich 18 mm plywood with strong class iii (1 panel size : 150 x 360 x 1.8 mm), girder gt 24, column waler srz 170 for column 150 x150 is save.

The beam casting process must be carried out together with the floor plate casting. Supporting equipment used for beam casting work includes concrete pumps, truck mixers, vibrators, work lights, and trowels. In the upper west project, the withdrawal of the prestress beam was carried out after the beam was cast. Prestress system to convert concrete into elastic material. Concrete that is not able to withstand tension and is strong enough to carry pressure is generally with high strength steel tensioned in such a way that the brittle load can carry the tensile stress. Because it has a special function, the concrete used for casting prestress beams is skirting concrete. Slump test and temperature test is carried out by admix and the qc of the upper west project to monitor and record the results. There is a casting monitoring sheet that must be filled in every time a casting is carried out with the aim that casting data can be recapitulated systematically. Based on the results of the concrete compressive strength test result analysis it can be concluded that the concrete used in prestressed beams with $f_c 45$ fulfil the requirements. The difference between the measurement and the reasonable calculation result is $\pm 7\%$ and the result of deviation calculation for PC 3 C1, C2, C3, C4 fulfil the requirement.


REFERENCES





- Abstrak, dkk, Aswani Ahmad, I., Anny Suryaningsih Taufieq, N., & Hamid Aras, A. (2009). *Analisis Pengaruh Temperatur terhadap Kuat Tekan Beton*.
- Asroni, A. (n.d.). *Kebutuhan Material Pada Perencanaan Portal Gedung Beton Bertulang di Wilayah Gempa 1 Dengan Sistem Elastik dan Daktail Penuh*.
- Munthe, A. T., & Noegroho, M. A. (2020). *Analysis of Strength, Stiffness, and Stability The Formwork Construction in LRT Jabodebek Project*. 2(2). <http://proceedings.worldconference.id>.
- Badan Standardisasi Nasional. (2011). SNI 03-1974-2011 Cara Uji Kuat Tekan Beton Dengan Benda Uji Silinder: Badan Standardisasi Nasional.
- Badan Standardisasi Nasional. (2019). *SNI 2847:2019 Persyaratan Beton Struktural Untuk Bangunan Gedung*. Jakarta.
- Badan Standardisasi Nasional. (2017). *SNI 2052:2017 Baja Tulangan Beton*. Jakarta.
- Badan Standardisasi Nasional Indonesia. (2019). *SNI 2847-2019: Persyaratan Beton Struktural untuk Bangunan Gedung*. Standar Nasional Indonesia, 8, 720.
- Yayasan Dana Normalisasi Indonesia. (1961). *Peraturan Konstruksi Kayu Indonesia (PKKI) NI-1961*. Bandung: Lembaga Penyelidikan Masalah Bangunan, Departemen Pekerjaan Umum dan Tenaga Listrik Yayasan Normalisasi Indonesia.
- PERI. (2017). *Variodeck Steel Waler Slab Table*. Germany: Formwork Scaffolding Engineering
- PERI. (2015). *Design Tables 2015 Formwork and Shoring*. Germany: Formwork Scaffolding Engineering



APPENDIX

NO. TM	PLAN	SIKAP				DEVIASI	BENTANG				VOL	BUTU BETON	AREA	BENDA USAHA					MIL SAMPEL	ADHUKIVE
		LOADING	DATANG	BENGEAR	SELESAI		SEKANG	SEKANG	SEKANG	SEKANG				1 HR	2 HR	24 HR	28 HR	CAD		
719	BSD	04.24	04.16	05.07	05.10		13				7.5	FC 45 FA 10% PLAT LT P1 ZONE 3								
733	BSD	04.17	05.21	05.25	07.01		13				7.5	SEKANG								
631	BSD	05.14	05.43	05.52	06.18		14				7									
719	BSD	06.23	06.45	07.00	08.24		13				7									
726	BSD	07.07	08.00	08.17	08.32		13	-	34.1	-	7									
738	BSD	08.10	08.25	08.28	08.41		13	-	34.1	-	7.5									
732	BSD	07.18	08.22	08.36	08.59		14	-	33.5	-	7.5									
731	BSD	07.14	08.27	08.29	08.08		13	-	34.2	-	7.5								1 1 2 2 6	
638	BSD	08.29	09.07	09.10	09.37		13	-	34.4	-	7	FC 35 FA 10% PLAT LT P1 ZONE 3								
767	BSD	08.29	09.20	09.45	10.13		12	-	33.2	-	7.5									
726	BSD	09.19	10.02	10.08	10.32		13	-	34.4	-	7									
719	BSD	09.23	10.08	10.15	10.35		12	-	34.5	-	7.5									
776	BSD	09.17	10.27	10.36	10.52		12	-	35.2	-	7									
736	BSD	10.16	10.56	11.01			13	-	35.1	-	7.5									



		(Nama Proyek)		
FMPTU-100 REV 1				
LAPORAN PENGECORAN BETON				
		Halaman :	Dari :	
DATA RENCANA PENGECORAN				
Tanggal	01-10-22	Perincian Volume Rencana (A)	Keterangan Dimensi Struktur (bila perlu lampirkan data perhitungan)	
Jam Rencana Pengecoran	23.50 - 11.01 (Start - Finish)	Pondasi		m ³
Item Pekerjaan	PLAT LT PI ZONE 3	Paes cap		m ³
Lokasi Pengecoran		Tie Beam		m ³
Luas (r)		Balok		m ³
Volume Rencana (r)		Plat lantai		180 m ³
Mutu Beton	FC 15+1-35 kg/cm ²	Kolom		m ³
Slump	12 ± 2 cm	Dinding		m ³
Additive		Tangga		m ³
Metode Pengecoran	TC-Bucket <u>Concrete Pump</u>	Lain-lain		m ³
Alat-alat Baru	VIBRATOR / LAMPU TL	QS Penanggungjawab data	paraf  Tgt 01/10	
REPORT PENGECORAN				
No. PPSbP	045	Masalah yang terjadi selama pengecoran		
No. SIB	045	1. Peralatan (apakah peralatan berjalan dg baik) BERJALAN DENGAN BAIK		
Kondisi Cuaca	Cerah Mendung / Hujan *	2. Material (apakah cycle kedatangan beton tertambat) KEDATANGAN BETON TERLAMBAT		
Keterangan Cuaca	CERAH	3. Personel (apakah supervisor & pekerja sudah terlatih) SUDAH TERLATIH		
Jam Mulai	23.50	4. Safety (apakah terjadi kecelakaan dalam bekerja) TIDAK TERJADI		
Jam Selesai	11.01	5. Lain-lain (apakah terjadi pelanggaran, seperti penambahan air) TIDAK TERJADI		
Jumlah Truk Mixer (yang datang ke proyek)	30			
Jumlah Truk Mixer (yang lolos Slump Test)				
Volume Beton (yang lolos Slump Test)	180,5 m ³ (a)			
Volume Actual (berdasarkan volume area yang dicor)	m ³ (b)			
Beton Downgrade	m ³ (c)			
Volume Waste	9,5 m ³ (d-A)			
Waste Total	5,28% ((d-A)/A)x100%			
Waste Pengecoran	5,28% ((d-A)/A)x100%			
(*) Cori yang Tidak Perlu				
Mengetahui (PM)		Disiapkan Oleh (Chief QA-QC/QC)		
Tanggal		Tanggal	09/10-22	

PPSP = Perincian Pekerjaan Sebelum Pengecoran (RUC/ST-012/R1)
 SIB = Surat Ijin Bekerja (FM/SPT-103)
 Status rencana sudah pernah pengecoran agar ditunjukkan

Downgrade = Material diterima namun untuk penggunaan lain (slump jatuh)
 Reject = Material yang tidak sesuai dicor & dikembalikan

Monev Hasil Evaluasi Hutan
 JE

TATA FMK-021/01 **DAFTAR MONITORING PENGECORAN UPPER WEST**

PROYEK : UPPER WEST
 Tipe Sampel (0)
 □ Kubus
 √ Silinder

NO	SUPPLIER	NOMOR KUBUS	JAM				SEVAID	SLUMP NORMAL	SLUMP INTRINSAL	SIRO NORMAL	SIRO INTRINSAL	VOLUME (M ³)	TGL COR	UMUR (HARI)	TANGGAL TES		JMLAH SAMPEL	LOKASI / ASAL PENGAMBILAN	KODE	MUTU BETON	ADITIF (kg/m ³)	LEMBAGA / TEMPAT TES	HASIL TEST (MPa)	%						
			LOADING	DATANG	BONGKAR	SELESAI									REKAMANA	REALISASI														
1	BSD	719	23.09	0.35	1.14	1.22	14		37.7		7.5	01 Oktober 2022	3	04 Oktober 2022	04 Oktober 2022	1	LT P1	PLAT LT P1 ZONE 3	FC 45 SCREENING			ACHMIX	26.39							
												7	08 Oktober 2022	10 Oktober 2022																
												14	15 Oktober 2022	15 Oktober 2022	1															
												21	22 Oktober 2022	24 Oktober 2022	1															
												28	29 Oktober 2022	01 November 2022	1															
												28	29 Oktober 2022	01 November 2022																
2	BSD	831	0.07	0.45	1.04	1.12	13		37		7																			
3	BSD	733	0.17	0.45	1.37	1.53	12.5		37.1		7.5	01 Oktober 2022	3	04 Oktober 2022	04 Oktober 2022	1	LT P1	PLAT LT P1 ZONE 3	FC 45 SCREENING			ACHMIX	26.86							
												7	08 Oktober 2022	10 Oktober 2022																
												14	15 Oktober 2022	15 Oktober 2022	1															
												21	22 Oktober 2022	24 Oktober 2022	1															
												28	29 Oktober 2022	01 November 2022	1															
												28	29 Oktober 2022	01 November 2022																
4	BSD	732	0.21	1.00	1.23	1.36	12		36.9		7.5																			
5	BSD	737	0.37	1.11	1.35	REJECT																								
6	BSD	732	1.06	1.40	REJECT																									
7	BSD	721	1.02	1.40	REJECT																									
8	BSD	796	1.26	1.54	2.02	3.40	11				7.5	01 Oktober 2022	3	04 Oktober 2022	04 Oktober 2022	1	LT P1	PLAT LT P1 ZONE 3	FC 45 SCREENING			ACHMIX	26.17							
												7	08 Oktober 2022	10 Oktober 2022																
												14	15 Oktober 2022	15 Oktober 2022	1															
												21	22 Oktober 2022	24 Oktober 2022	1															
												28	29 Oktober 2022	01 November 2022	1															
												28	29 Oktober 2022	01 November 2022																
9	BSD	716	1.46	2.22	REJECT																									
10	BSD	796	1.07	2.23	2.40	3.20	13				7.5																			
11	BSD	831	2.11	2.45	3.21	4.18	14				7																			
12	BSD	804	2.32	2.57	3.41	4.18	14				7																			
13	BSD	700	3.39	4.16	4.29	4.50	13				7.5																			
14	BSD	1108	3.40	4.10	4.20	4.40	14				7	01 Oktober 2022	3	04 Oktober 2022	04 Oktober 2022	1	LT P1	PLAT LT P1 ZONE 3	FC 45 SCREENING			ACHMIX	22.65							
												7	08 Oktober 2022	10 Oktober 2022																
												14	15 Oktober 2022	15 Oktober 2022	1															
												21	22 Oktober 2022	24 Oktober 2022	1															
												28	29 Oktober 2022	01 November 2022	1															
												28	29 Oktober 2022	01 November 2022																
15	BSD	688	3.58	4.31	4.44	4.52	13				7																			
16	BSD	718	4.14	4.61	4.59	5.20	12				7.5																			
17	BSD	719	4.15	4.56	5.07	5.28	13				7.5																			





PT. MIXINDO ABADI KARYA
 Head Office & Laboratory
 Jl. Masjid Baiturrahim No. 73 BINTARO Tangerang Selatan - Banten 15222.
 Telp. : +62 21 276 596 17 Fax: +62 21 276 596 17


LAPORAN HASIL PENGUJIAN KUAT TEKAN

NOMOR LAPORAN : 04068 / TB / MAK-LAB / X / 2022
 Report Number
DIBUAT UNTUK : PT TATAMULIA NUSANTARA INDAH
 Executed for
PROYEK : UPPER WEST APARTEMENT
 Project
JENIS BENDA UJI : SILINDER Ø 15 x 30 cm
 Type of Specimen
TANGGAL PENDAFTARAN : 20 Oktober 2022
 Registration

No	Kode	Tanggal		Umur (hari)	Luas Penampang (cm ²)	Berat (kg)	Beban (kN)	Kuat Tekan MPa (N/mm ²)	Pola Retak	Keterangan
		Cor	Uji							
1	TATA - UW / PLAT LT.P1 ZONE 3 / FC 45 SCREENING / TM 719	01/10/22	24/10/22	23	176,71	12,40	800	45,27	3	
2	TATA - UW / PLAT LT.P1 ZONE 3 / FC 45 SCREENING / TM 733	01/10/22	24/10/22	23	176,71	12,41	780	44,14	3	
3	TATA - UW / PLAT LT.P1 ZONE 3 / FC 45 SCREENING / TM 796	01/10/22	24/10/22	23	176,71	12,39	795	44,99	3	
4	TATA - UW / PLAT LT.P1 ZONE 3 / FC 45 SCREENING / TM 11086	01/10/22	24/10/22	23	176,71	12,40	770	43,57	3	
5	TATA - UW / PLAT LT.P1 ZONE 3 / FC 45 SCREENING / TM 796	01/10/22	24/10/22	23	176,71	12,42	805	45,55	3	




* [ASTM C-39/C 39M-04a]




Pilih Pola Retak sesuai gambar dibawah ini :








Bintaro, 24 Oktober 2022
 Laboratorium Beton

[Signature]
DR. PRIGANAP TUA NAIBAHO, ST, MT
 Kepala Laboratorium

Stressing Record Sheet OVM System			
Project : UPPER WEST		Beam Names _____	
: BSD			
Client : PT. TATAMULIA NUSANTARA INDAH		pc-3	
Date stressed : _____			
Type of work : Prestressed Concrete Beam			
Equipment details		Stressing details	
Manometer No : 03	Jack type : SJ300	Tendon Identification : C-1	Tendon type : OVM13-15
Jack Capacity : 3000 kN	Ram area of Jack : 577.3 cm ²	Dia. of strand : 12.7 mm	Nominal area of strand : 98.71 mm ²
		Ultimate Tensile Strength : 184 kN	Beam length : _____ meter
		Tendon length : 15,900 meter	Jacking Force : 75-0/6 / 138 kN
Compressive Strength		Pressure : 1347 psi	Tendon Elongation : 99.3 mm
At 28 days : _____ N/mm ²	At transfer : _____ N/mm ²		
Pressure reading (psi)	Incremental Extension (mm)	Total Extension (mm)	Deviation Calculation
1000	5		$\frac{1347}{4347} (87 - 6) = 99.6 \text{ MM.}$ $D = \frac{99.6 - 99.3}{99.3} \times 100$
2000	25		
3000	44		
4000	64		
5000	84		
1347	92	92 - 5 = 87	
			$D = + 0.3 \%$
PT. MULTISTRAN ENGINEERING		 Stressing Operator	Date: 02/11-22
PT. TATAMULIA NUSANTARA INDAH			 Checked by
CONSTRUCTION MANAGEMENT		 Acknowledged by	

Stressing Record Sheet OVM System			
Project : UPPER WEST		Beam Names _____	
Client : PT. TATAMULIA NUSANTARA INDAH		PC-3.	
Date stressed : _____			
Type of work : Prestressed Concrete Beam			
Equipment details		Stressing details	
Manometer No : 03	Jack type : SJ300	Tendon Identification : C-2	Tendon type : OVM13-15
Jack Capacity : 3000 kN	Ram area of Jack : 577.3 cm ²	Dia. of strand : 12.7 mm	Nominal area of strand : 98.71 mm ²
		Ultimate Tensile Strength : 184 kN	Beam length : _____ meter
		Tendon length : 15.900 meter	Jacking Force : 75% / 138 kN
Compressive Strength		Pressure : 5347 psi	Tendon Elongation : 99.3 mm
At 28 days : _____ N/mm ²	At transfer : _____ N/mm ²		
Pressure reading (psi)	Incremental Extension (mm)	Total Extension (mm)	Deviation Calculation
1000	5		$\frac{5347}{4347} (89 - 4) = 202,1 \text{ MM}$ $\Delta = \frac{202,1 - 99,3}{99,3} \times 100$
2000	25		
3000	45		
4000	66		
5000	86		
5347	94	94 - 5 = 89	
			$\Delta = + 2,8 \%$
PT. MULTISTRAN ENGINEERING		 Stressing Operator	Date: 02/11/22
PT. TATAMULIA NUSANTARA INDAH			 Checked by
CONSTRUCTION MANAGEMENT		 Acknowledged by	

Stressing Record Sheet OVM System			
Project : UPPER WEST		Beam Names _____	
Client : PT. TATAMULIA NUSANTARA INDAH		PC. 3.	
Date stressed : 02-11-2022			
Type of work : Prestressed Concrete Beam			
Equipment details		Stressing details	
Manometer No : 03	Tendon Identification : C. 3 -	Tendon type : OVM13- 15	
Jack type : SJ300	Tendon length : 15,900 meter	Dia. of strand : 12.7 mm	
Jack Capacity : 3000 kN	Jacking Force : 75. % / 138 kN	Nominal area of strand : 98.71 mm ²	
Ram area of Jack : 577.3 cm ²	Pressure : 5347 psi	Ultimate Tensile Strength : 184 kN	
Compressive Strength		Tendon Elongation : 101,8 mm	
At 28 days : _____ N/mm ²			
At transfer : _____ N/mm ²			
Pressure reading (psi)	Incremental Extension (mm)	Total Extension (mm)	Deviation Calculation
1000	5		$\frac{5347}{4347} (89. - 6) = 102,1 \text{ MPa}$ $D = \frac{102,1 - 101,8}{101,8} \times 100$ $D = + 0,28 \%$
2000	25		
3000	45		
4000	66		
5000	86		
5347	94	94 - 5 = 89	
PT. MULTISTRAN ENGINEERING		 Stressing Operator	Date: 02/11-22
PT. TATAMULIA NUSANTARA INDAH			 Checked by
CONSTRUCTION MANAGEMENT		 Acknowledged by	

Stressing Record Sheet OVM System			
Project : UPPER WEST		Beam Names _____	
Client : PT. TATAMULIA NUSANTARA INDAH		PC. 3.	
Date stressed : 02-11-2022			
Type of work : Prestressed Concrete Beam			
Equipment details		Stressing details	
Manometer No : 63	Jack type : SJ300	Tendon Identification : C.4	Tendon type : OVM13-15
Jack Capacity : 3000 kN	Ram area of Jack : 577.3 cm ²	Dia. of strand : 12.7 mm	Nominal area of strand : 98.71 mm ²
		Ultimate Tensile Strength : 184 kN	Beam length : _____ meter
		Tendon length : 15.900 meter	Jacking Force : 75% / 138 kN
Compressive Strength		Pressure : 5347 psi	Tendon Elongation : 101.8 mm
At 28 days : _____ N/mm ²	At transfer : _____ N/mm ²		
Pressure reading (psi)	Incremental Extension (mm)	Total Extension (mm)	Deviation Calculation
1000	5		$\frac{5347}{4347} (88 - 6) = 100,86 \text{ MM}$ $D = \frac{100,86 - 101,8}{101,8} \times 100$
2000	25		
3000	45		
4000	66		
5000	86		
5347	93	93 - 5 = 88	$D = -0,9\%$
PT. MULTISTRAN ENGINEERING		 Stressing Operator	Date: 02/11-22
Checked by			Date: 02/11-22
PT. TATAMULIA NUSANTARA INDAH		 Checked by	Date: 02-11-2022
Acknowledged by			Date: 02-11-2022

PROJECT : BALOK PRESTRESS UPPER WEST
 LOCATION : BSD
 ITEM : BALOK PRESTRESS

LIST PROPOSAL OF STRESSING BALOK PRESTRESS (75% UTS)

Name of Beam	Name of Tendon	Tendon Length (m)	Strand in Tendon	Jacking Force per strand		Manometer Pressure (psi)	Elongation Estimated (mm)	Stressing Direction	Compressive Strength f _c (Mpa)	Jack Type	Ram Area (cm ²)	Stressing Order	Prosentase
				(kN)	% UTS								
PC-1	C1	13.895	12	138.00	75	4291	87.5	One side	45	SJ-300	577.3	I	100%
	C2	13.895	12	138.00	75	4291	87.5	One side	45	SJ-300	577.3	II	100%
	C3	13.895	11	138.00	75	3934	89.5	One side	45	SJ-300	577.3	III	100%
	C4	13.895	11	138.00	75	3934	89.5	One side	45	SJ-300	577.3	IV	100%
PC-2	C1	18.550	19	138.00	75	6734	111.8	One side	45	SJ-300	577.3	I	100%
	C2	18.550	19	138.00	75	6734	111.8	One side	45	SJ-300	577.3	III	100%
	C3	18.550	18	138.00	75	6375	115.6	One side	45	SJ-300	577.3	II	100%
	C4	18.550	18	138.00	75	6375	115.6	One side	45	SJ-300	577.3	IV	100%
PC-3	C1	15.900	15	138.00	75	5347	99.3	One side	45	SJ-300	577.3	I	100%
	C2	15.900	15	138.00	75	5347	99.3	One side	45	SJ-300	577.3	II	100%
	C3	15.900	15	138.00	75	5347	101.8	One side	45	SJ-300	577.3	III	100%
	C4	15.900	15	138.00	75	5347	101.8	One side	45	SJ-300	577.3	IV	100%
PC-4	C1	16.050	15	138.00	75	5347	100.2	One side	45	SJ-300	577.3	I	100%
	C2	16.050	15	138.00	75	5347	100.2	One side	45	SJ-300	577.3	III	100%
	C3	16.050	12	138.00	75	4291	102.7	One side	45	SJ-300	577.3	II	100%
	C4	16.050	12	138.00	75	4291	102.7	One side	45	SJ-300	577.3	IV	100%
PC-5	C1	15.900	14	138.00	75	5013	99.2	One side	45	SJ-300	577.3	I	100%
	C2	15.900	14	138.00	75	5013	99.2	One side	45	SJ-300	577.3	II	100%
	C3	15.900	12	138.00	75	4291	101.6	One side	45	SJ-300	577.3	III	100%
	C4	15.900	12	138.00	75	4291	101.6	One side	45	SJ-300	577.3	IV	100%
PC-6	C1	18.550	14	138.00	75	5013	116.4	One side	45	SJ-300	577.3	I	100%
	C2	18.550	14	138.00	75	5013	116.4	One side	45	SJ-300	577.3	III	100%

Notes: Perhitungan pressure (psi) berdasarkan hasil interpolasi kalibrasi Jack SJ-300 - 03

PT. MULTISTRAN Engineering

CALCULATION OF PC STRAND ELONGATION

PROJECT TITLE : UPPER WEST BSD
 ITEM : PC-3 C1 C2 2xGVMI13-15

Coefficient of friction (μ) 0.200
 Coefficient of Wobble (K) 0.0020
 Draw in (δ) 6.0 mm
 Jacking Force (one PC strand) 138.00 kN
 Ratio of jacking force to UTS 75.000 % UTS
 Elasticity modulus of PC strand (E) 195.00 kN/mm²
 PC Strand area of cross section 98.71 mm²
 Ultimate Tensile Strength (UTS) 184.00 kN
 1000 hour Relaxation of PC strand 2.50 %

Stressing from left side

segment no	length (m)	drage length	y _a (m)	y _b (m)	1/R	(μxR+Kx)	e	delta		area								
								cum left	cum right	left (1)	right (1)	left (2)	right (2)	left (3)	right (3)			
								1.0000	0.0000									
1	0.475	0.475	1.0450	1.0450	0.0000	0.999050		0.9991	0.0000	0.475	0.000	0.475					0.475	
2	0.700	0.700	1.0450	1.0450	0.0000	0.998601		0.9977	0.0000	0.699	0.000	0.699					0.699	
3	1.350	2.700	1.0450	0.9140	0.1438	0.959335		0.9571	0.0000	1.319	0.000	1.319					1.319	
4	7.650	15.300	0.9140	0.1400	0.0265	0.945756		0.9052	0.0000	7.123	0.000	7.123					7.123	
5	4.775	15.300	1.0450	0.1400	0.0309	0.961668		0.8705	0.0000	4.239	0.000	4.239					4.239	
Length :																		
Free :										13.856	0.000	13.856	0.000	13.856	0.000			
Bond :										99.3	0.0	99.3	0.0	99.3	0.0			
Total :										15.900								

TENDON ELONGATION :

- single end stressing :
 left end extension = 99.3 mm

SH - 26 / 10 / 2022
 17 : 55 : 31.00